

BATTERY PARK CITY AUTHORITY

Project: 200 Rector Street – Interior Fit Out Contractor Services
Date: October 7, 2016
RE: Addendum #3
Total Pages: 1

The following revisions and/or clarifications are to be made to the Request for Proposals for “200 Rector Street – Interior Fit Out Contractor Services.” This Addendum provides answers to questions received through September 30, 2016. All questions received by September 30, 2016 will be answered by October 7, 2016.

Questions/Answers *

Detail 1/A-108 is not indicated on any other drawings - please tell me where this detail in [sic] supposed to occur.
DETAIL TO OCCUR AT ALL WINDOWS. EACH POCKET WILL BE INDIVIDUAL (NOT CONTINUOUS) AT EACH WINDOW.

Louvers in details 3,4 & 5/A-108 all appear to go above ceilings [sic] please confirm that this is correct. **YES, THAT IS CORRECT**

How do the F6 led light fixtures integrate with our 2x2 ceiling? **AT EACH LIGHT FIXTURE RUN, EXTEND CROSS TEES ON BOTH SIDES OF LIGHT FIXTURES TO PARTITIONS CREATING AA “DUTCHMAN” LIKE SITUATION.**

Details A-108 indicate louvers [sic] on window #3 & # 10. Floor Plan A-101 indicates window #2 & #7 with Louvers. Please clarify which windows are getting louvers. **LOUVERS ARE LOCATED ABOVE WINDOWS 2 & 10, AND MAIN ENTRY DOOR. SEE DWG. M.102.00**

Is there a BMS contractor for this project or is it stand-alone?
ANSWER: WE DO NOT HAVE A BMS CONTRACTOR FOR THIS PROJECT.

* Submitted questions printed in italics followed by answers in bold print

By signing the line below, I am acknowledging that all pages of Addendum #1 have been received, reviewed and understood and will be incorporated into the bid price submitted. This document must be attached to the Proposal for consideration.

Print Name

Signature

Date

Number of pages received: 1